



Power Gen Set Up - Klassic - LTKL 12-P



Self bunded double wall design with below features:

- Designed to be lifted by Crane or Forklift for simple handling
- Stackable up to 3 high
- Small foot print
- 3 x 1" feed and return lines with connections
- Letter box openings for hose connections so that Roller Door remains closed during operation
- Fluid level dipstick for tank and interstitial space
- Vent pipe for tank and interstitial space
- Suction foot valve, overfill protection and electronic overfill alarm
- Access manway, Foldable ladder
- Warranty - 5 years structural, 1 year on valves (conditions apply)

Specifications

Description

Safe Fill, litres	11,115
Length, mm	2,991
Width, mm	2,438
Height, mm	2,896
Tare Weight, kg	4,300
Vent Pipe	Standard
Fluid Level Dipstick	Standard
Compliance	AS1940, AS1692, AS1657, UL142, CSC, BS799 Part 5



Disclaimer: Information and photographs shown are for marketing purposes only. Actual product may vary to images shown due to continual improvement processes, design changes and optional extras

GLOBAL CONTACTS

MIDDLE EAST : +971 50 719 7137 | ASIA : +61 430 531 448 | AFRICA : +27 82 611 1484

SOUTH AMERICA: +56 9881 85513